Mount Carmel Area School District

CORRINA M. LESKO
BUSINESS MANAGER
600 W 5TH ST
MOUNT CARMEL PA 17851-1897
PHONE: 570-339-1500 FAX: 570-339-0487

Bid Request

The Mount Carmel Area School District is seeking bids for a Walk-In Freezer/Cooler in our High School kitchen. Specifications may be found on the School District's website:

Walk-In Cooler Specs

Bids can be mailed to Pete Cheddar, Superintendent, Mount Carmel Area School District, 600 W 5th Street, Mount Carmel, PA 17851 or emailed to leskoc@mca.k12.pa.us, and must be received by 12:00 p.m., Wednesday, June 3, 2026.

The School Board reserves the right to make awards by individual item, group of items, all or none, or a combination thereof; to reject any and all bids, or waive any minor irregularity or technicality for the best interest of the School District. The School Board also reserves the right to make awards to one, or more vendors. EOE

BALLY REFRIGERATED BOXES INC Model # INDOOR STRUCTURE # 54345

Bally Prefabricated Exterior Dimensions: 19'-3"(1) x 13'-0¼"(w) x 8'-6"(h)

2 Compartments 1 Tiers Ceiling: Single Span Panel Thickness: With Floor 4" Floor 4 in. Exterior Vertical Used (7'-10") with 4 in. Partition, 4 in. Floor, 4 in. Ceiling

Comments: Base Finish Vertical and Ceiling Panels: Embossed Galvalume (26 GA)

Special Finishes: Exterior Door - Stainless Steel 22 Ga. (Smooth) Exterior Door Frame

Stainless Steel 22 Ga. (Smooth) Interior Ceiling - Smooth Aluminum Interior Door - Stainless Steel 22 Ga. (Smooth) Interior Door Frame Stainless Steel 22 Ga. (Smooth) Interior Floor - Aluminum Treadplate .125" Thick Partition I-Interior Partition - Smooth Aluminum Partition Interior Partition2 - Smooth Aluminum

Wall l - Exposed Exterior Verticals - Stainless Steel 22 Ga. (Smooth)

Wall 1- Interior Verticals - Smooth Aluminum

Wall 2- Interior Verticals - Smooth Aluminum

Wall 3- Interior Verticals- Smooth Aluminum

Wall 4- Interior Verticals - Smooth Aluminum Doors/Openings:

Wall I Door 1 (1) 36" x 78" Hinged Door In a 46"

Wall l Door 2 (1) 36" x 78" Hinged Door In a 46"

Accessories and Extras:

(2) 48" LED KEIL 48x754-CL-N Light- 40° F to 100° F(Range)

(2) 8" Oversized Thresholds

(2) Foot Treadle

(I) Kason High Flow PRP #086980 - 4" Panels

(14) L/F Vinyl Rub Rail (Grey Color) Snub Nose Profile

(37) S/F Stainless Steel (22 ga)(Closure Metal)

(1) Strip Curtain (36" Door and Under) (In stock) Kason

Floor Options: Each Total (270) S/F 3/4" Plywood Foamed

BALLY REFRIGERATED BOXES INC Model No.

(1) BEZA 008 H9 HS2EB (208-230/1/60) w/ smart speed Scroll Unit 8550 BTU/h

(1) BEZA 025 L9 HS2EB (208-230/1/60) w/ SMARTY AP+ For use with A2L Evap's Required after 1/1/26
(I) BLP209LE-S2E9 SV+ 208-230/1/60 SmartVap+ Electric Defrost with A2L Leak Sensors Installed

(1) BLP210MA-SlE9 SV+ 115/1/60 SmartVap+ Air Defrost with A2L Leak Sensors Installed

(I) DR200 Compressor Stand - GL Galvanized Base 3 1 ea BALLY REFRIGERATED BOXES INC Model No. Weight: 6,660.56

BALLY REFRIGERATED BOXES INC Model No. 01 HP System (5 yr. Parts, I yr. Labor)

BALLY REFRIGERATED BOXES INC Model No. 02.5 HP System (5 yr. Parts , 1 yr. Labor)

Installation of unit will need to be Prevailing Wage

Mt Carmel Jr/Sr High School Combination Walk-In Install -Prevailing wage-

A2L Combo box 19’3”x 13’ x 8’6”

Scope of work:

- Demo and dispose of existing walk-in and refrigeration
- Erect new combination walk-in cooler/freezer with floor
- Hang and wire ceiling lights
- Set refrigeration condensing units and hang evaporators
- Install condensate drains
- Install insulated refrigeration line sets up to 25’
- Leak check refrigeration systems with 100 psi dry Nitrogen
- Perform control wire connections to refrigeration equipment if needed
- Charge and commission refrigeration systems with A2L refrigerant