BALLY REFRIGERATED BOXES INC Model # INDOOR STRUCTURE # 54345

Bally Prefabricated Exterior Dimensions: 19'-3"(1) x 13'-0¼"(w) x 8'-6"(h)

2 Compartments 1 Tiers Ceiling: Single Span Panel Thickness: With Floor 4" Floor 4 in. Exterior Vertical Used (7'-10") with 4 in. Partition, 4 in. Floor, 4 in. Ceiling

Comments: Base Finish Vertical and Ceiling Panels: Embossed Galvalume (26 GA)

Special Finishes: Exterior Door - Stainless Steel 22 Ga. (Smooth) Exterior Door Frame

Stainless Steel 22 Ga. (Smooth) Interior Ceiling - Smooth Aluminum Interior Door - Stainless Steel 22 Ga. (Smooth) Interior Door Frame Stainless Steel 22 Ga. (Smooth) Interior Floor - Aluminum Treadplate .125" Thick Partition I-Interior Partition - Smooth Aluminum Partition Interior Partition2 - Smooth Aluminum

Wall l - Exposed Exterior Verticals - Stainless Steel 22 Ga. (Smooth)

Wall 1- Interior Verticals - Smooth Aluminum

Wall 2- Interior Verticals - Smooth Aluminum

Wall 3- Interior Verticals- Smooth Aluminum

Wall 4- Interior Verticals - Smooth Aluminum Doors/Openings:

Wall I Door 1 (1) 36" x 78" Hinged Door In a 46"

Wall l Door 2 (1) 36" x 78" Hinged Door In a 46"

Accessories and Extras:

(2) 48" LED KEIL 48x754-CL-N Light- 40° F to 100° F(Range)

(2) 8" Oversized Thresholds

(2) Foot Treadle

(I) Kason High Flow PRP #086980 - 4" Panels

(14) L/F Vinyl Rub Rail (Grey Color) Snub Nose Profile

(37) S/F Stainless Steel (22 ga)(Closure Metal)

(1) Strip Curtain (36" Door and Under) (In stock) Kason

Floor Options: Each Total (270) S/F 3/4" Plywood Foamed

BALLY REFRIGERATED BOXES INC Model No.

(1) BEZA 008 H9 HS2EB (208-230/1/60) w/ smart speed Scroll Unit 8550 BTU/h

(1) BEZA 025 L9 HS2EB (208-230/1/60) w/ SMARTY AP+ For use with A2L Evap's Required after 1/1/26
(I) BLP209LE-S2E9 SV+ 208-230/1/60 SmartVap+ Electric Defrost with A2L Leak Sensors Installed

(1) BLP210MA-SlE9 SV+ 115/1/60 SmartVap+ Air Defrost with A2L Leak Sensors Installed

(I) DR200 Compressor Stand - GL Galvanized Base 3 1 ea BALLY REFRIGERATED BOXES INC Model No. Weight: 6,660.56

BALLY REFRIGERATED BOXES INC Model No. 01 HP System (5 yr. Parts, I yr. Labor)

BALLY REFRIGERATED BOXES INC Model No. 02.5 HP System (5 yr. Parts , 1 yr. Labor)

Installation of unit will need to be Prevailing Wage

Mt Carmel Jr/Sr High School Combination Walk-In Install -Prevailing wage-

A2L Combo box 19’3”x 13’ x 8’6”

Scope of work:

- Demo and dispose of existing walk-in and refrigeration
- Erect new combination walk-in cooler/freezer with floor
- Hang and wire ceiling lights
- Set refrigeration condensing units and hang evaporators
- Install condensate drains
- Install insulated refrigeration line sets up to 25’
- Leak check refrigeration systems with 100 psi dry Nitrogen
- Perform control wire connections to refrigeration equipment if needed
- Charge and commission refrigeration systems with A2L refrigerant